

fischer  [®]
innovative solutions



Effective Installation of natural stone Facade


- Introduction (BWM)
- Possibilities of the fixation of natural stone facades
- Acceragate the effectivity
 - Installation
 - Reducing time & costs
- Some referals

Introduction to BWM Fassadensysteme GmbH

We are not selling cars ...



we are selling, producing and advising



BWM: Concepting, Advicing architects and installers, calculation in statics and building physics, detail planning ...



BWM Fassadentechnik GmbH

Headquarter is placed in Leinfelden
(near Stuttgart)



Production is placed in Gorleben
(between Hamburg & Hannover)



Different methods of fixing natural stone panels on the facade

- **Visible Fixing**

- Screwing
- Hooks
- Clamps

- **Unvisible Fixing**

- clamps
- Glueing
- Towels
- Undercut anchor

Visible Fixed : 1. Screwing

Mockup for a project in Andorra



Arguments for this system:

- Thin and small panels
- Irregular forms and overlapping areas
- Very „exotic“ kind of art

Visible Fixed : 1. Screwing

Project driven system



Small description :

- Using an steel panel for support
- Slates have to be predrilled

Visible Fixed : 2. Hooks

Project near Stockholm (power station)




Arguments for this system

- Thin and small slates
- Vertical mounting
- „Loving hooks“

Visible Fixed : 2. Hooks

System ATK 104



Small description

- Predrilled slated will be fixed by stainless steel – coloured - hooks

Visible Fixed : 3.a) Clamps

Bornholm, Centre of sustainability



Arguments for using this system


- Thin and small slates
- Vertical mounting
- Short time of installation
- Reducing installation costs

08.11.2018

Effective Installation of natural stone facade, Stefan Schrag
Fischer/ BWM

Visible Fixed : 3.a) Clamps

System ATK 100 KL




Small description

[03-04-2017 ATL100-
KL 1980dpi Cam-001.mp4](#)

Visible or invisible fixing : 3. b) Clamps

Limestone project



Arguments for this system

- Visible fixing for slates < 13 mm
- Invisible fixing for slates > 15 mm. Precondition is the stone has to be slotted

Visible or invisible fixing : 3. b) Clamps

Limestone project



Small description

- Clamps in stainless steel are fixed in a „special vertical rail profile“
- High grade of „prefabrication“ is possible

Unvisible fixing : 4 Glueing

Nordea Bank, Copenhagen




Arguments for glueing

- Two kinds of installation
 - Glueing on the the building side
 - Glueing prefabricated
- Special blank rails
- Glueing certifications, tests are necessary & installation team has to be trianed up in glueing
- Prefabrication is almost necessary

Unvisible fixing : 4 Glueing

ATK 100



Small description

- Take care and observe the regulations of the supplier, in case of ..
 - Humidity
 - Temperature
 - Dust
 - Period of time ...

Unvisible fixing : 4 Glueing

Glueing process the four steps



Small description

- Cleaning
- Primering
- Taping
- Glueing

Unvisible fixing : 4 Glueing


Certification



Small description


- Certificated test allows the using of the combination (Natural stone- Glueing material – Aluminium Substructure)

Flow chart for glued projects



Unvisible fixing : 5 Dowels

Certification




Argumentation for dowels

- Traditional method

Unvisible fixing : 5 Dowels

No BWM system !!



Argumentation against dowels

- „Stress“ forces for the natural stone panel
- A lot of complaints regarding of the spalling at the edges of the natural stone panels

Unvisible fixing : 6 Horizontal system & Undercut anchor

Russia, Grasnodar Stadium




Argumentation for undercut anchor

- High loads
- More stressfree forces for naturalstone
- Many options for realization of details

Unvisible fixing : 6 Horizontal system & Undercut anchor

Mounting Sequence




Argumentation for undercutanchor

- Installation of the vertical subframe
- Fixing of the clasps with undercutanchor *)
- Hang in
- Optimizatzize the position of the panel

Unvisible fixing : Fixing of the clasps with undercut anchor *)

Installation of the undercut anchor




Undercut hole in the panel material





Undercut anchor

Argumentation for undercut anchor




Rus- Moscow Krasnoproletarskaja


Russian detail planning



Detail corner



Detail planning - ceiling



The result .. Krasnoproletarskaja, Moscow




Pre- fabrication

CAD- Drawings (i.e. architect)



„Translation“ into subframe system




Pre- fabrication

Shipping package



Operating instructions



Pre- fabrication

PV Project in Trondheim



PV Project in Oslo




Pre- fabrication

Requirements for this jobsite

- Building is closed to the main train station → traffic !
- The installation time for the natural stone panels was from 22:00 – 5 :00 o`clock

For hang in the prefabricated panels

Project Stockholm Orgelpipan



Pre- fabrication

„Enviromental situation“: no space



Project Stockholm Orgelpipan



Pre- fabrication :

- Reduction of the total mounting time of the facade (ca.30 %)
- Optimizing of material supply and waste (10 % less material)
- Permanent transparence of the costs / cost controlling
- small tolarences on the building side

referrals

Al Hamra Kuwait



Technical description

- Natural Stone
- 15.000 sqm
- Undercut Anchor

referrals

Russia, Grassnodar Stadium,



Technical description

- Natural Stone
- 35.000 sqm
- Undercut Anchor
- Stainless steel subframe

referrals

„Enviromental situation“: no space



Al Hamra Kuwait

- Natural Stone
- 15.000 sqm
- Undercut Anchor


referrals

USA New York Warren Street



Technical description

- Natural Stone (Jura Limestone)
- 13.000 sqm
- Prefabricated



referals

Chile Santiago de Chile Bahá ì Temple



Technical description

- Translucent Natural Stone & Glass
- 11.000 sqm
- Undercut Anchor


referrals

Mexico, Jumex Museo



Technical description

- Natural Stone (Granite)
- 5.800 sqm



referrals

United Kingdom London Houndsditch



Technical description

- Internal using
- Natural stone fixed under different angles

referrals

France Paris La Defence



Technical description

- Ceiling and facade
- 25.000 sqm
- Refurbishment

referrals

China Beijing new government district




Technical description

- Natural Stone (Granite)
- 700.000 sqm
- Undercut fixed

Last topic ...

Building physical aspects



Technical description

To achieve the technical requirements of the building physical aspects, we have to reduce the coldbridges of the substructures

Last topic ...

Requirements

- The requirements of the international regulations and rules are growing !
- In several European countries the Buildings have to achieve Passivhouse Standard !

.. We fulfill it 😊

Certificate
Certified Passive House component
for cool, temperate climate, valid until 31.12.2014

Passive House Institute
Dr. Wolfgang Feist
64283 Darmstadt
GERMANY

Category: Facade anchor
Manufacturer: BWM Dübel- und Montagetechnik GmbH
70771 Leinfelden- Echterdingen
Product name: ZeLa bracket
with stainless steel guide bar

The following criteria were used in awarding this certificate:

Efficiency Criterion
In two typical applications*, the construction fulfills the requirements of
 $\Delta U_{wb} \leq 0.010 \text{ W/(m}^2\text{K)}$

Comfort Criterion
The inner surface must be warm enough to prevent mould as well as uncomfortable down-draught and radiation losses.
 $\theta_{Lmin} \leq 17^\circ\text{C}$


Thermal data of the certified component

ZeLa	thermal bridge coefficient χ [W/K]	minimum inner surface temperature θ_{Lmin} [°C]
Fixed point	0.0101	19.34
Sliding point	0.0065	19.39
Fixed point small	0.0065	19.39


* The criterion has been validated with two representative buildings a row house and a school building.

www.passivehouse.com


CERTIFIED COMPONENT
Passive House Institute



Isothermal map of the fixed point



Isothermal map of the sliding point



Representation of the fixed point



Thank you very much for your attention !

